

**HARRIS COUNTY
UTILITY DISTRICT NO. 15
REHABILITATION OF SANITARY SEWER LINES
TO SERVE
GREENFIELD VILLAGE, SECTION ONE AND TWO
UNIT BID TABULATION**

ENGINEER'S ESTIMATE: \$250,000.00

BID DATE: November 19, 2009

ITEM	DESCRIPTION	QUANTITY	UNIT	A & A CABLE CONTRACTORS, INC.		COKER PIPELINE REHABILITATION, INC.		BC LINER, LLC	
				BIDDER NO. 1 UNIT PRICE	AMOUNT	BIDDER NO. 2 UNIT PRICE	AMOUNT	BIDDER NO. 3 UNIT PRICE	AMOUNT
<u>SANITARY SEWER REHABILITATION</u>									
1.	Pre-Rehabilitation Cleaning and Television Inspection of 8-Inch Sanitary Sewer Pipe	9,441	LF	\$1.00	\$9,441.00	\$4.05	\$38,236.05	\$1.25	\$11,801.25
2.	Pre-Rehabilitation Cleaning and Television Inspection of 10-Inch Sanitary Sewer Pipe	269	LF	\$1.00	\$269.00	\$4.20	\$1,129.80	\$1.25	\$336.25
3.	Install Cured-in-Place Pipe Liner in Existing 8-Inch Sanitary Sewer Pipe (6 MM min. thickness)	9,441	LF	\$19.00	\$179,379.00	\$17.25	\$162,857.25	\$20.50	\$193,540.50
4.	Install Cured-in-Place Pipe Liner in Existing 10-Inch Sanitary Sewer Pipe (6 MM min. thickness)	269	LF	\$24.00	\$6,456.00	\$18.00	\$4,842.00	\$21.50	\$5,783.50
5.	Sanitary Sewer Service Connection or Re-Connection - Internal or External (whichever method is necessary to re-establish service)	215	EA	\$1.00	\$215.00	\$45.00	\$9,675.00	\$50.00	\$10,750.00
6.	Post-Rehabilitation Television Inspection of 8-Inch Sanitary Sewer Pipe	9,441	LF	\$1.00	\$9,441.00	\$0.50	\$4,720.50	\$0.25	\$2,360.25
7.	Post-Rehabilitation Television Inspection of 10-Inch Sanitary Sewer Pipe	269	LF	\$1.00	\$269.00	\$0.50	\$134.50	\$0.25	\$67.25
8.	Point Repair (all pipe sizes and types and all depths; only as approved and authorized by the Engineer)	10	EA	\$900.00	\$9,000.00	\$500.00	\$5,000.00	\$1,300.00	\$13,000.00
9.	Remove and Replace Existing Sanitary Sewer Clean Out	8	EA	\$500.00	\$4,000.00	\$500.00	\$4,000.00	\$800.00	\$6,400.00
10.	Trim Protruding Sanitary Sewer Service Connections as Required for Liner Installation	5	EA	\$200.00	\$1,000.00	\$150.00	\$750.00	\$175.00	\$875.00

**HARRIS COUNTY
UTILITY DISTRICT NO. 15
REHABILITATION OF SANITARY SEWER LINES
TO SERVE
GREENFIELD VILLAGE, SECTION ONE AND TWO
UNIT BID TABULATION**

ENGINEER'S ESTIMATE: \$250,000.00

BID DATE: November 19, 2009

ITEM	DESCRIPTION	QUANTITY	UNIT	A & A CABLE CONTRACTORS, INC.		COKER PIPELINE REHABILITATION, INC.		BC LINER, LLC	
				BIDDER NO. 1 UNIT PRICE	AMOUNT	BIDDER NO. 2 UNIT PRICE	AMOUNT	BIDDER NO. 3 UNIT PRICE	AMOUNT
11.	Obstruction Removal (grease, roots, etc.)	5	EA	\$150.00	\$750.00	\$125.00	\$625.00	\$150.00	\$750.00
	TOTAL AMOUNT BID: (do not include supplemental items)				\$220,220.00		\$231,970.10		\$245,664.00
	Calendar Days				120		60		180
	<u>SUPPLEMENTAL ITEMS</u>								
1.	Remove and Replace 4-Inch Thick Reinforced Concrete Sidewalk or Driveway (maximum bid price \$9.00/SF)	50	SF	\$9.00	\$450.00	\$10.00	\$500.00	\$9.00	\$450.00
2.	Remove and Replace 6-Inch Thick Reinforced Concrete Sidewalk or Driveway	50	SY	\$9.00	\$450.00	\$30.00	\$1,500.00	\$30.00	\$1,500.00
3.	Remove and Replace Cast Iron Manhole Ring (maximum bid price \$350.00/EA)	2	EA	\$350.00	\$700.00	\$350.00	\$700.00	\$350.00	\$700.00
4.	Remove and Replace Cast Iron Manhole Cover (maximum bid price \$200.00/EA)	2	EA	\$200.00	\$400.00	\$200.00	\$400.00	\$200.00	\$400.00
5.	Radio Detection of Existing Service Location (maximum bid price \$150.00)	3	EA	\$150.00	\$450.00	\$150.00	\$450.00	\$150.00	\$450.00
6.	Remove and Replace Existing Mature Landscape Shrub	5	EA	\$200.00	\$1,000.00	\$300.00	\$1,500.00	\$350.00	\$1,750.00
7.	Remove and Replace Existing Landscape Tree	5	EA	\$250.00	\$1,250.00	\$1,250.00	\$6,250.00	\$1,500.00	\$7,500.00
8.	Remove and Replace Existing Fence (all types)	200	LF	\$5.00	\$1,000.00	\$27.50	\$5,500.00	\$30.00	\$6,000.00

NOTE: ALL SUPPLEMENTAL ITEMS ARE TO BE IMPLEMENTED ONLY AT THE DIRECTION OF THE ENGINEER.